



Republic of the Philippines
LEYTE NORMAL UNIVERSITY
Tacloban City

Project Title : REPAIR OF ELEVATED FLOORING AT I.T. LABORATORY
Location : Leyte Normal University, Tacloban City
Duration : 45 calendar days
Amount : ₱ **423,269.25**

SCOPE OF WORKS

1 GENERAL REQUIREMENTS

- Contractor shall provide equipment for Clearing, Hauling and Disposal of Wastes/Garbage and Debris. Should perform General Cleaning including vacuum cleaning of all interior floors and walls
- The Contractor may utilize water and power from the University with corresponding compensation through sub-meters or similar devices, or pay for water and electric consumption depending on a special agreement between both parties.

2 ARCHITECTURAL WORKS

- Provide and install using Marine Plywood 3/4 or Phenolic Board 3/4 drive with Assorted Nails and Screws
- Provide and install using good lumber and angle bars for bracing and framing for flooring support
- Provide and use Rubberized Flooring for floor finishes