

**BILL OF QUANTITIES**  
**HRDC GYM FLOOR REPAIR**  
 LEYTE NORMAL UNIVERSITY  
 TACLOBAN CITY  
 Project Duration: **30 CD**

ITEM NO.	DESCRIPTION	QTY.	UNIT	UNIT COST			AMOUNT
				Materials	Labor	Total	
<b>1</b>	<b>FLOOR COATING IN REPLACEMENT OF DEFECTIVE TILES</b>						
	a MATERIALS						
	Rubber Based Floor Coating (Slipless) (Navy Blue)	108	gal/s				₱ -
	Sealer (as recommended by Floor Coating product)	54	gal/s				-
	4" Baby Roller w/ Handle	5	pcs				-
	Mixing Pan	3	pcs				-
	Paint Brush 2"	2	pcs				-
	Paint Brush 1"	2	pcs				-
	Portland Cement	40	bag/s				-
	Washed Sand	4	cu.m.				-
							-
	<b>Material Cost</b>						-
	<b>Sub-total "1a"</b>						₱ -
	b LABOR COST						
	b.1 Floor Preparation						
	- Removal of Defective Tiles & Disposal	1297	sq.m.				-
	- Resurfacing of Cement mortar mix to desired floor level	1297	sq.m.				-
	- Application of Floor Sealer (1 coat)	1297	sq.m.				-
	b.2 Application of 2-coats Floor Coating	2594	sq.m.				-
	<b>Labor Cost</b>						-
	<b>Sub-total "1b"</b>						₱ -
<b>2</b>	<b>PLYWOOD TEMPORARY FLOORING AT STAGE</b>						
	a MATERIALS						
	18mm THK. MARINE PLYWOOD	75	shts				-
	1 1/2" wood screw	1350	pcs				-
	Flatwall Enamel	15	gal/s				-
	Gloss Enamel	15	gal/s				-
	Paint Thinner	2	gal/s				-
	Body Filler (Easy Tite)	15	gal/s				-
	4" Baby Roller w/ Handle	10	pcs				-
	Mixing Pan	3	pcs				-
							-
	<b>Material Cost</b>						-
	<b>Sub-total "2a"</b>						₱ -
	b LABOR COST						
	b.1 Installation of Plywood Flooring	214	sq.m.				-
	b.2 Application of 2-coats Floor Coating	428	sq.m.				-
	b.3 Repair of Stage Risers	1	lot				-
	<b>Labor Cost</b>						-
	<b>Sub-total "2b"</b>						₱ -
<b>3</b>	<b>WALL EXTENSION AT REAR AREA OF GYM</b>						
	a MATERIALS						
	5mm THK. Marine Plywood	39	shts				-
	2" x 2" x 8' Coco Lumber	96	ea				-
	CWN 4"	3	kg				-
	CWN 2"	3	kg				-
	CWN 1"	3	kg				-
	Flatwall Enamel	10	gal/s				-
							-
	<b>Material Cost</b>						-
	<b>Sub-total "3a"</b>						₱ -

