



Republic of the Philippines
LEYTE NORMAL UNIVERSITY
Tacloban City

Project Title : Construction of the Centennial Marker
Location : Leyte Normal University, Tacloban City
Duration : 90 CD
Amount : ₱ **499,920.29**

SCOPE OF WORKS

1 SITE WORKS

- All excavations shall conform to the lines and grades shown on the approved plans or as established by the Engineer. It shall be finished to reasonably smooth and will not be disturbed. uniform surfaces. Excavation operations shall be conducted so that structures or materials outside the limits Barricades shall be placed around open excavations and danger or warning signs shall be provided.

2 CONCRETE WORKS

- Provide concrete works on the design's floor, base, stand, globe, stairs, and concrete humanoid sculpture as indicated on the plan.

3 REINFORCING BARS

- Provide Reinforced Steel Bars for the floor, base, stand, globe, stairs.
Provide GI Pipe for the Laurel leaves design

4 ARCHITECTURAL WORKS

- Provide 6" thk. Machine press concrete Hollow Block including 12mm0 RSB for vertical and horizontal reinforcement.
- Provide Plain cement plaster in on base, globe, stairs. Concrete humanoid sculpture should continent should be embossed be plastered properly.
- Provide skimcoat and painting works shown
- Provide plates, logos, letterings, designs, etc
- Provide mechanical works for eternal flames
- Provide 4 solar lights faces to the globe
- Provide foundation planting