



Republic of the Philippines
LEYTE NORMAL UNIVERSITY
Tacloban City

Project Title : REPAIR AND REPLACEMENT OF FLOOR TILES OF HALLWAY AT I.T. BUILDING
Location : Leyte Normal University, Tacloban City
Duration : 45 CD
Amount : ₱ **296,599.63**

SCOPE OF WORKS

1 GENERAL REQUIREMENTS

- Contractor shall provide equipment for Clearing, Hauling and Disposal of Wastes/Garbage and Debris. Should perform General Cleaning including vacuum cleaning of all interior floors and walls
- The Contractor may utilize water and power from the University with corresponding compensation through sub-meters or similar devices, or pay for water and electric consumption depending on a special agreement between both parties.

2 ARCHITECTURAL WORKS

- Provide and install 60 x 60 Glazed Tiles along the hallway and should use Tiles Adhesive type c2 and Tile grout and Epoxy Sealer. Material to use should be checked and approve by university president.
- All chipped tiles should be inform first by the university end users or on project control engineer and should be disposed properly